

CORRECTED ADDENDUM #1

CITY OF FAIRBANKS
HAMILTON ACRES SNOW STORAGE FENCING
ITB-18-13

ISSUED: September 20, 2018

This **Addendum #1** becomes part of ITB 18-13 –Hamilton Acres Snow Storage Fencing. This addendum may modify the original ITB. All other terms and conditions remain the same.

ADD THE FOLLOWING:

B. FENCE SPECIFICATIONS:

- Approximate footage: 837', bidder responsible for verifying measurements
- 8' 9 gage fence with 2" 1.2 oz galvanized
- 2 7/8" SS-40 end posts driven 60" in ground
- 2 3/8" SS-40 line posts driven 48" in ground
- 7 gage tension wire top and bottom
- 9 gage steel ties and hog rings
- 1 5/8" bracing
- NO privacy slats

ACKNOWLEDGE RECEIPT OF ADDENDUM:

NAME OF COMPANY	
NAME	TITLE
SIGNATURE	DATE
ADDRESS	CITY, STATE, ZIP
PHONE	E-MAIL

Return to Purchasing Agent via email to purchasing@fairbanks.us or fax (907) 459-6731.