Classroom 2 Closet (Marked F on floor plan)

- Remove sink and vanity.
- Demo overhead lights.
- Demo outlet near sink and all non-code electrical fixtures.

Contractor to protect existing facility from potential damage. Any damage to existing facility, shall be repaired at contractor's expense.

202-4.01 METHOD OF MEASUREMENT. *ADD the following paragraph:*

The material and work will not be measured for payment and will be Lump Sum.

202-5.01 BASIS OF PAYMENT. *DELETE the first paragraph and substitute the following:*

Item 202.0001.1. Payment will be for all work plans, materials, labor, appurtenances, equipment, supervision, coordination, and incidentals that are necessary for removing and disposing of all material and debris encountered and as shown in the plans and described in the specifications.

ADD the following:

Payment will be made under:

Pay Item Pay Unit

202.0024.1 Demolition and Hazardous Materials Abatement

Lump Sum

SECTION 622 REST AREA FACILITIES

622-2.13 MATERIALS. *ADD the following paragraphs:*

The contractor selected will provide all services necessary to design and furnish specified work and materials specifications in accordance with the standards in this Invitation to Bid. Furnish and install the following parts to construct complete and functioning ADA restrooms, closets, lights, and classrooms as shown on the plans:

Restroom 1 (Marked B on Floor Plan)

- Install new reconfigured stall wall and doors to incorporate an ADA accessible stall.
 - o Install new restroom partitions and all hardware.
 - o Install new ADA restroom partitions and all hardware.
- Install three new toilets. Install maximum number of ADA toilets the space will allow.
- Install new handrails in ADA stall.
- Install sink vanity from restroom 2.
- Install new ADA compliant sink.
- Install two new mirrors above sink.
- Install new toilet paper holders in each stall.
- Install soap dispenser at each new sink, one at ADA required height.
- Install new paper towel dispenser near each new sink, one at ADA required height.